

Proposal Release #4

Proposal Package Name	Proposal Package Description
Proposal Package 33a - Interior Ornamental Metals (CANCELLED)	
Proposal Package 33b - Interior Glass & Glazing	The scope of this package includes furnish and install aluminum door frames, hollow metal door frame glass and glazing, aluminum fixed windows, decorative glass, glass doors, and ticket windows. Work is located at the main stadium and at exterior gate structures.
Proposal Package 35 - Epoxy Resinous Flooring	The scope of this package includes furnish and install all resinous flooring, integral base, and accessories. Work includes surface preparation, material application, and temporary protection following cure.
Proposal Package 36 - Carpet & Resilient Flooring	The scope of this package includes furnish and install all carpet flooring, resilient flooring, athletic flooring, base, and accessories. Access flooring and static control flooring shall be furnished and installed by this Bid Package. Work includes surface preparation, material application, and temporary protection following cure.
Proposal Package 40b - Site Work/Stone	The scope of this package includes furnish and install all site concrete paving, site retaining walls including all related excavation and footings. In addition to, furnish and install all cast-in-place stairs, all perimeter seat walls including related foundations and excavation and all site stone benches and shingles.
Proposal Package 40c - Site Work - Ornamental Metals/Fencing/Railing	The scope of this package includes furnish and install fencing at the site perimeter including anti-climbing fence, parking lot gates and all architectural fencing including at outbuildings. Furnish and install all bollards on site, including concrete fill as needed. Furnish and install corten fence and all site railings and metals.
Proposal Package 40g - Site Work - Site Electrical (Lighting & Power)	The scope of this package includes providing LV raceway Trenching excavation, & backfill. All site lighting, all site power requirements, excluding HV and Utility Service entrance work.
Proposal Package 40i - Site Work - Landscape & Irrigation	The scope of this package includes furnish and install all plantings and landscaping, including mulch, bioretention plantings, shrubs and turf surfaces inclusive of all soils and mulch. Furnish and install exterior synthetic turf surfaces, and the irrigation system. Relocate decorative boulders from the existing stadium to the new stadium.

<p>Proposal Package 41a - Signage Exterior</p>	<p>The scope of this package includes furnish and install all exterior (site) signage. Work excludes stadium sponsorship signage. Signage includes: staff entries, site identification, gate identification, vehicular directional, parking lot identification, and entrances. Work also includes, layout, required foundations / supporting structure, fabrication, and installation.</p>
<p>Proposal Package 41b - Signage Interior</p>	<p>The scope of this package includes furnish and install all interior signage. Work excludes stadium sponsorship signage. Signage includes: directional, graphic, room identification, regulatory, section, and ADA. Work also includes, layout, support, fabrication, electrical coordination, and installation.</p>
<p>Proposal Package 42 - Toilet Partitions/Accessories</p>	<p>The scope of this package includes furnish and install toilet partitions and accessories. Partitions are stainless, phenolic, and plastic. Work includes furnishing and installing all toilet, bath, and laundry accessories (excluding any identified as OFOI).</p>
<p>Proposal Package 43 - Specialties</p>	<p>The scope of this package includes furnish and install specialties within Division 10. Specialties include: Metal Lockers, Fire Extinguisher Cabinets, Defibrillator Cabinets, High Density Storage / Mobile Shelving, Markerboards, Cubicle Tracks and Curtains, and Corner Guards.</p>
<p>Proposal Package 46a - Parking Lot Paving - West of Abbott</p>	<p>The scope of this package includes furnish and install all standard and heavy duty asphalt paving including all subbase preparation necessary, all parking lot line striping, all gravel lots including subbase preparation. In addition to, furnish and install all curbs and islands within the parking lots.</p>
<p>Proposal Package 57 - Window Treatments</p>	<p>The scope of this package includes furnish and install all curtains, track, brackets, draperies, roller window shades, motors, and accessories. Draperies / shades are manual and motorized.</p>