

BID RELEASE #2, GROUPING 2

BID PACKAGE NAME	BID PACKAGE DESCRIPTION
BID PACKAGE 11A – Exterior Glass & Glazing (Entrances)	The scope of this package includes furnish and installation of all exterior aluminum framed entrances / storefronts (GL1T, GL4T), exterior aluminum / glass doors (GL1T, GL4T), associated door hardware (GL1T), glazed aluminum curtain wall systems (GL1, GL4, GL4L, & GL6), aluminum windows, and louvers within exterior wall systems enclosing the building. Engineering is delegated design and the responsibility of the trade partner. Provide all firestopping and waterproofing tie-ins at exterior walls.
BID PACKAGE 11B – Perforated Metal Panel System & Colonnade Wrap	The scope of this package includes furnish and installation of all exterior façade perforated metal panels (MP1) (above the thin brick precast façade) and perimeter colonnade wraps (MP4) at each radial grid line. Engineering is delegated design and the responsibility of the trade partner.
BID PACKAGE 11C – Architectural Precast System	The scope of this package includes furnish and installation of all exterior façade architectural precast with thin brick (BRK1) and other exterior precast façade (PC1) elements. Engineering is delegated design and the responsibility of the trade partner.
BID PACKAGE 11D – Metal Panels	The scope of this package includes furnish and installation metal panel system at top of exterior wall at edge of canopy (MP6). Engineering is delegated design and the responsibility of the trade partner.
BID PACKAGE 12 – New Stadium Site Utilities (Excluding Smoke Creek Line)	The scope of this package is to furnish and install water, sanitary, and storm systems outside of the stadium. Excluded from this package is any water, sanitary, and storm work included in BP#03a and BP#03b bid packages. Also, excluded is site underground electrical work.
BID PACKAGE 13 – Concrete on Metal Deck	The scope of this package is to furnish and install all superstructure fill-on-metal deck / cast-in-place concrete, topping slabs, stair pan fills, curbs, stadia aisle site cast steps, stadia overbuild platform slabs, and grouting of structural steel column base plates.